BENGALURU SOLID WASTE MANAGEMENT LIMITED

Office of the Deputy General Manager-2 (BSWML), 1st Floor, BBMP Building, Thimmaiah Road, Vasanth Nagar, Bengaluru-560 052.

****

No. DGM-3/(BSWML)/Tend/04/Adde- 01/25-26 Date:21.06.2025

ADDENDUM-1

Subject: "Operation and Maintenance of 120 TPD Wet Waste Processing Plant located at Seegehalli"

Sl. No	Tender Document Reference	Clarifications/Amendments issued
1	INVITATION FOR TENDER (IFT), Page-03 No.DGM-3/BSWML/TEND/03/2025-26 Date: 30.05.2025	INVITATION FOR TENDER (IFT), Page-03 No.DGM-3/BSWML/TEND/04/2025-26 Date: 30.05.2025
2	The Assignment is expected to commence at Seegehalli MSW Processing Plant: Actual O&M will commence within 7 days from the date of agreement becoming effective.	The Assignment is expected to commence at Seegehalli MSW Processing Plant: Actual O&M will commence **within 15 days** from the date of agreement becoming effective.
3	GENERAL CONDITIONS OF CONTRACT: **2.2 Commencement of Services** The Consultants shall begin carrying out the Services within thirty (30) days after the date the Contract becomes effective, or at such other date as may be specified in the SC.	GENERAL CONDITIONS OF CONTRACT: **2.2 Commencement of Services** The Consultants shall begin carrying out the Services within **Fifteen (15) days** after the date the Contract becomes effective, or at such other date as may be specified in the SC.
4	**SECTION 5. TERMS OF REFERENCE** 1. AN OUTLINE OF THE TASKS TO BE CARRIED OUT The inward quantity of the waste at processing plant recorded by weigh bridge shall be considered as actual. It is to be noted that up to 125% of the input quantity incoming as prescribed	**SECTION 5. TERMS OF REFERENCE** 1. AN OUTLINE OF THE TASKS TO BE CARRIED OUT The inward quantity of the waste at processing plant recorded by weigh bridge shall be considered as actual. It is to be noted that, **the successful bidder shall process the incoming waste during**

	quantity shall be processed by bidder as per accepted rate of proposal. If the inward quantity is less than the prescribed quantity of plant, the same shall be processed & payment shall be done to selected bidder as per the actual quantity received at plant. The payment of processing shall be made as per the payment schedule.	**seasonal variations which can be up to 125% of 120 TPD. Payment shall be done to selected bidder as per the actual quantity received at plant as per the payment schedule.**
5	**a)Qualification Criteria** 1. Achieved in at least two financial years a minimum annual financial turnover of Rs.970.02 Lakhs. In case of Joint Venture the combined turnover should meet the criteria. 2. The bidder / JV should collectively have satisfactorily completed at least one work of similar nature in MSWM of value not less than Rs. 242.51 lakhs in any one year during last five years or (50% of the estimated cost for one year). or The bidder / JV should collectiveiy have supplied manpower for value not less than Rs. 242.51 lakhs for O&M of a MSW processing plant in any one year during last five years or (50% of the estimated cost for one year). 3. The bidder / JV should collectively have successfully completed processing of Wet Municipal solid waste of 35040 MT quantity in any one year during last five years (80% of the estimated waste quantity). or The bidder / JV should collectively have supplied minimum manpower of 32 numbers for O&M of a Wet MSW processing plant of minimum 120TPD capacity/ producing compost from MSW (80% of estimated manpower requirement).	**a)Qualification Criteria** 1. Achieved in any two financial years during the last five financial years **(i.e. 2019-20 to 2023-24)** minimum annual financial turnover of **Rs. 970.02 Lakhs.** (10% weightage would be given per annum to bring the amount to the present financial year) In case of Joint Venture the combined turnover should meet the criteria. 2. The bidder / JV should **individually/ collectively** have satisfactorily completed at least **one similar nature of work in Operation and Maintenance of MSW Wet waste processing plants** of value not less than **Rs. 242.51 lakhs** in any one year during last five years or (50% of the estimated cost for one year). or The bidder / JV should individually/ collectively have satisfactorily supplied manpower for value not less than **Rs. 242.51 lakhs** for O&M of **MSW wet waste** processing plant in any one year during last five years or (50% of the estimated cost for one year (10% weightage would be given per annum to bring the amount to the present financial year) 3. The bidder / JV should collectively have successfully completed processing of Wet Municipal solid waste of **35040 MT** quantity in any one year during last five years **(i.e. from 2020-21 to 2024-25)** or (80% of the estimated waste quantity). Or The bidder / JV should collectively have supplied minimum manpower of **32 numbers** for O&M of a Wet MSW processing plant of minimum 120 TPD capacity/ producing compost from MSW (80% of estimated manpower requirement).

	3. PREPARATION OF PROPOSAL **3.3 Financial Turnover** of previous years indicated in clause 3.3 (viii) (b) above shall be given a weightage of 10% per year to bring them to the price level of 2024-25.	Note: **Financial Turnover and Value of similar nature of work** of previous years indicated in clause 3.3 shall be given a weightage of 10% per year to bring them to the price level of Current year.
6	SECTION 5. TERMS OF REFERENCE 3. AN OUTLINE OF THE TASKS TO BE CARRIED OUT: The waste received at the facility shall be treated adopting aerobic windrow composting process and the rejects shall be sent to the landfill	SECTION 5. TERMS OF REFERENCE 3. AN OUTLINE OF THE TASKS TO BE CARRIED OUT: The waste received at the facility shall be treated adopting aerobic windrow composting process and the **inerts** shall be sent to the landfill.
7	SECTION 5. TERMS OF REFERENCE 3. AN OUTLINE OF THE TASKS TO BE CARRIED OUT: The task assigned to the selected bidder is to receive the wet waste at plant, process it and dispose the rejects as stated in the procedures below	SECTION 5. TERMS OF REFERENCE 3. AN OUTLINE OF THE TASKS TO BE CARRIED OUT: The task assigned to the selected bidder is to receive the wet waste at plant, process it and dispose the **inerts** as stated in the procedures below
8	3.6 (ii) Qualification Criteria (a) Eligibility criteria -lead member to have experience mentioned in criteria as specified in 3.3 (vii) (a)	3.6 (ii) Qualification Criteria (a) Eligibility criteria -Joint Venture to have experience mentioned in criteria as specified in 3.3 (vii) (a)
9	Section 5: Terms of Reference- iv. Providing Odour & Flies Control, fogging for Seegehalli MSW Processing Plant: It is the responsibility of bidder to ensure that no nuisance of odour & flies is observed within plant and its vicinity of minimum 3km radius. Daily spraying and fogging arrangements need to be provided as per the directions of plant manager. The list of chemicals (indicative) is as follows:	Section 5: Terms of Reference- iv. Providing Odour & Flies Control, fogging for Seegehalli MSW Processing Plant: It is the responsibility of bidder to ensure that no nuisance of odour & flies is observed within plant **and its vicinity of the plant. Daily spraying and fogging arrangements need to be provided as per the directions of plant manager in and around in the processing plant based on the spreading of the odour, which can go up to 3 kms radius**. The list of chemicals (indicative) is as follows:
10	**3I - Joint Venture Format** Whereas the Managing Director, BSWML Karnataka State the ' Employer' has invited proposal for appointment of agency Operation and Maintenance of 150 TPD wet waste processing plant located at	**3I - Joint Venture Format** Whereas the Managing Director, BSWML Karnataka State the ' Employer' has invited proposal for appointment of agency Operation and Maintenance of 120 TPD wet waste processing plant located at Seegehalli – hereinafter called the Project.

	Lingadheeranahalli – hereinafter called the Project.	
11	**3I (A) Power of Attorney of Authorised Signatory (*)** all such acts, deeds and things as are necessary or required in connection with or incidental to submission of our application for pre-qualification and submission of our bid for 'Operation and Maintenance of 150 TPD wet waste processing plant located at Lingadheeranahalli	**3I (A) Power of Attorney of Authorised Signatory (*)** all such acts, deeds and things as are necessary or required in connection with or incidental to submission of our application for pre-qualification and submission of our bid for 'Operation and Maintenance of 120 TPD wet waste processing plant located at Seegehalli.
	To be read as in continuation with the existing RFP:	
12		**section 5:** **vii. A. Leachate Management.** The generated leachate from windrow is collected in the collection tank If farmers are requesting/demand for Fermented liquid organic manure (FLOM) then farmer's RTC and request letters to be taken for the records. FLOM shall be transported scientifically with the approval of competent authority. Leachate can be recirculated for maintenance of moisture purpose in the windrow as per the SOP without affecting the performance of the plant and without creating any nuisance. If demand is not available then leachate can be transported to designated LTP. Ensure that Collected leachate should not over flow from the tank and to be cleared within 2 days of generation.
13	**Section 5. Terms Of Reference** ix. Payment Schedule of Contract Price	Additional Note: 4 The concession period for the project is set at two years, with 5% increment in tipping fee for the second year.

All the bidders are requested to participate in the bidding process and further the bidders are instructed to note the above clarifications/amendments issued and to kindly note that the **last date of submission is up to 30-06-2025 at 16:00 hours.**

Deputy General Manager
BSWML

Deputy General Manager-3
BSWML